

DECISIONS DURING CONSTRUCTION PHASE LEAD TO REDUCED WASTE AND HUGE SAVINGS

WHAT HAPPENED?	A project to part-convert, part-new build a business park had plenty of scope to minimise waste by identifying opportunities early on. The project was fairly large, with a floor area of 2682m² and a total cost of £1,750,000.
OUTCOME	Targets to reduce waste by 10%, recycle 60%, and send no more that 25% to landfill were easily achieved. 140 tonnes of inert waste was forecast, but no inert waste was sent from site during construction, and non-hazardous waste was only 38 tonnes. Mixed waste leaving site easily achieved a recycling rate of 60%.
	These waste reductions helped the project enjoy a significant cost saving of $\pounds34,899$ – the equivalent of 2% of the total project costs.
CONTEXT	Several decisions were taken during the construction phase to help reduce waste and save money, including: Crushing and reusing material from the demolition phase Recycling timber waste on site in the biogas boiler Reusing inert material arisings for bunds on site Reusing existing paved areas
LESSONS LEARNT	 The significant saving in costs was achieved with decisions during construction. The main lessons learnt were: Segregated skips will always be considered for future projects as they reduce costs Only waste contractors with high offsite recycling rates will be used, to ensure best practice and reduction of waste to landfill In-house forecasting data will be developed to ensure pre-construction plans align as closely as possible to actual waste arisings data Further improvements will be sought through addressing the procurement strategy